

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-357

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T 47N	R 24W	A-12
	T 47N	R 25W	M-12
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

1993 DEC 29 AM 10:39
MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORDING
REGISTER OF DEEDS
1 PAGE 54
LIBER Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Thursday, December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12: Quarter Corner common to Section 31, T47N-R24W and Section 36, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
 12" Hemlock S33W, 40 1.
 10" Maple N34E, 32 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Traversed and found a wood post 2.5 ft. North of the mean position on line between the NW and SW corners of Section 31. No original evidence was found. Set a Marquette County survey monument at the mean position and on line between the NW and SW corners of Section 31. Distances North and South measure 2659.14'. No original G.L.O. evidence found. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify corner referenced by nails in:
 6" Maple N10E 18.25 ft.
 9" Maple N75E 29.64 ft.
 17" Hemlock S58E 17.65 ft.
 10" Hemlock S10W 21.92 ft.
 Monument is 0.5 ft. above ground.
 Bk. 3, Pg. 158

Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589

