

1893

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-358

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code =#
1. Public Land Survey	T47N R24W	A-13
	T47N R25W	M-13 ✓
	T46N R24W	A-1
	T46N R25W	M-1
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1993 DEC 29 AM 10:30
REGISTER OF DEEDS
MARQUETTE COUNTY MICHIGAN
RECEIVED FOR RECORD
LIBER 1 PAGE 55
Register of Deeds Stamp # File Number

I, GERALD W. CARLSON, in a field survey on Thursday, December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>A-13: Section Corner common to Section 31, T47N-R24W; Section 6, T46N-R24W; Section 1, T46N-R25W; and Section 36 T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 16" Hemlock S85W, 22 l 26" Hemlock N18E, 54 l</p>	<p>1980 - G. Carlson set a 4" diameter by 36" concrete monument from evidence of the remains of a wood post at the correct bearing and distance N85E 22 l from a Hemlock stump. This position also checks with the remains of the Hemlock line tree 840 ft. to the East. Referenced by 12" Maple, S16W, 23.82 ft. 8" Maple, S80E, 18.44 ft. 4" Tw. Maple, N45E, 22.03 ft. 8" Tw. Maple, N71W, 37.06 ft. L1 RC, Pg. 21</p>
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found G. Carlson concrete monument as set in 1980.
Replaced with a Marquette County Survey Monument.
Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced concrete monument with 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
14" Maple S16W 23.78 ft. Carlson NBT
8" Maple S80E 18.48 ft. Carlson NBT
4" Maple N45E 22.03 ft. Carlson NBT
10" Twin Maple N71W 37.00 ft. Carlson NBT
Monument is 0.8 ft. above ground.
Bk. 3, Pg. 156

Signed by Gerald W. Carlson Date 12-23-93
Surveyor's Michigan License No. 24589

