

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1994 DEC 28 PM 5:57

JOB NUMBER: 94030  
SHEET NO. : 1-509  
For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Patricia L. Manley*  
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code ##
1. Public Land Survey	T 47N R 27W T 47N R 26W	M-3 A-3 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 175  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3: NE Corner of Section 12. 9" Sugar N10E 12 1  
 1844: William A. Burt's original survey notes describe the 16" Sugar S65E 08 1  
 corner monument as a post referenced by; No date given: MAAS coordinates indicate the NE corner of  
 7" Birch N37W 4 1 Section 12, T47N-R27W as South 5087.85 and West 4998.79.  
 20" Sugar S75E 8 1  
 1845: Sam Hill's original subdivision survey notes for  
 T47N-R26W indicate the following additional references for  
 the NW corner of Section 7, T47N-R26W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position calculated from early 1900 Maas Mine coordinate values from two found corners 1/2 mile North and South. Distance South is 2640.26' (2640.59' Maas) and distance North is 2618.45' (2618.79' Maas). This corner falls in the side slope of the old Jackson Mine pit.

RATIFIED BY PEER GROUPE  
P.A. 345 OF 1990

*Larry J. Bussard*  
DATE Dec 19, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2' long 3/4" re-rod capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
 4" White Birch S76W 17.07 ft.  
 4" White Birch N75W 23.67 ft.  
 5" White Birch N54W 22.10 ft.  
 3" White Birch S76E 33.68 ft.  
 Steel sign post West 1.5 ft.  
 Monument is flush with ground, positioned on steep side slope of old mine pit and grouted in place.  
 Bk. 8, Pg. 65

Signed by Gerald W. Carlson Date 12-28-94  
 Surveyor's Michigan License No. 24589

