

1994 DEC 28 PM 5:57

JOB NUMBER: 94030

SHEET NO. : 1-507

For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE (County) Located In: Corner Code #

1. Public Land Survey T 47N R 27W M-5  
T 47N R 26W A-5 ✓  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Patricia A. Monney*  
REGISTER OF DEEDS

LIBER 1 PAGE 173  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Wednesday, December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5: NE Corner of Section 13. 8" Hemlock N27E 10 l  
 1844: William A. Burt's original survey notes describe the 17" Sugar S55E 08 l  
 corner monument as a post referenced by: 1913: C.C.I. Company coordinate list for NE Corner of  
 16" Sugar S62E 7 l Section 13 indicates an iron pipe with coordinates South  
 10" Fir N54W 33 l 10342.34 and West 4897.63.  
 1845: Sam Hill's original subdivision survey notes for No date given: MAAS coordinates for SE Corner Section 12,  
 T47N-R26W indicate the following additional references for T47N-R27W indicates South 10342.34 and West 4897.63.  
 the NW Corner of Section 18, T47N-R26W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position calculated from early 1900 Maas Mine coordinate values from two found corners 1/2 mile North and South. Distance South is 2626.20' (2626.87' Maas) and distance North is 2611.71' (2612.62' Maas).

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Bessard*  
DATE Dec 19, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 3/4" re-rod grouted in rock capped with a 3 1/4" diameter aluminum tablet Marquette County Survey  
 Monument stamped to identify the corner referenced by nails in:  
 12" Twin Maple N05W 33.08 ft.  
 7" Hemlock N33E 50.82 ft.  
 5" Balsam S50E 23.19 ft.  
 4" Maple S24W 32.20 ft.  
 Steel sign post West 7.4 ft.  
 Monument is 0.30' above ground and set in a rock knob.  
 Bk. 8, Pg. 71



Signed by Gerald W. Carlson  
Surveyor's Michigan License No. 24589

Date 12-28-94