

1994 DEC 28 PM 5: 57

JOB NUMBER: 94030
SHEET NO. : 1-500

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in:

_____ MARQUETTE _____ (County)	Located In:	Corner Code \neq
1. Public Land Survey	T 47N R 27W M-12 T 47N R 26W <u>A-12</u>	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Patricia A. Hanley
REGISTER OF DEEDS

LIBER 1 PAGE 170
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Thursday, December 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-12: East 1/4 Corner of Section 36.
1844: William A Burt's original survey notes describe the corner monument as a post referenced by:
6" Spruce S52W 8 1
10" Spruce N56W 18 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position established equidistant and on line between the Northeast and Southeast corners of Section 36. Distances South and North are 2596.12'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2' long, 3/4" diameter re-rod capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
9" Spruce S62W 163.52 ft.
5" Oak N84W 143.93 ft.
6" Twin Balsam S76E 124.13 ft.
Easterly Power Pole in group of 3 North 76.82 ft.
Steel sign post South 1.0 ft.
Monument is 0.30' above ground and approximately on centerline of power line.
Bk. 8, Pg. 35

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE Dec 19, 1994

Signed by Gerald W. Carlson Date 12-28-94
Surveyor's Michigan License No. 24589

