

**SURVEY &  
REMONUMENTATION**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE  
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 28 PM 5:58

*Patricia A. Monberg*  
REGISTER OF DEEDS

JOB NUMBER: 94030  
SHEET NO. : 1-514

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>26W</u>	<u>C1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **1** PAGE **180**  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Friday, December 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-1: Section Corner common to Sections 5 and 6.  
1845: Sam Hill's original survey notes described the corner monument as a wood post one chain East of the Corner common to Sections 31 and 32, T48N-R26W.  
Referenced by:  
8" Fir, S6E, 06 1  
16" Maple, S74W, 39 1

Survey map recorded in Liber 278, Page 252, filed by Ray J. Brotherton, LS #6780, indicates the corner common to Sections 31, 32, 5 and 6 as an iron. No corner accessories given.  
1966: Survey map recorded in Liber 282, Page 229, filed by Ray J. Brotherton indicates the Section Corners common to 31, 32 and Sections 5 and 6. No corner accessories given.  
(See reverse side.)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Corner position established at GLO offset distance of 66.00' East of the Southwest Corner of Section 32, T48N-R26W and on line between the Southwest and South 1/4 Corners of Section 32. Distance West is 2631.235' and distance East is 2620.87'.

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**  
*Larry J. Bussone*  
DATE Nov 7, 1994

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
10" White Birch S86W 28.88 ft.  
10" Oak S23W 35.58 ft.  
15" Oak N77E 18.64 ft. (cluster of 3 trees)  
8" Maple N40E 29.03 ft.  
Steel sign post North 2.1 ft.  
Monument is 0.65' above ground.  
Bk. 6, Pg. 145

Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589



Record No. 514:

Part "A" Continued:

1986: Certificate of Survey by Larry Bussone, RLS #25833 recorded in Liber 358, Page 585, indicates the Corner common to Sections 31, 32 and 5 and 6. No corner accessories given.

1989: A Land Corner Recordation Certificate filed by Allan Pierce, LLS #30097, indicates a capped 1/2" rebar established by utilization of C.C.I.C. furnished coordinates referenced to the 1/4 Corner common Section 31 and 6. Reference by:

4" Poplar,	N38°E,	35.66'
10" Poplar,	S21°W,	13.39'
8" Cherry,	S78°E,	3.77'
9" Poplar,	N84°W,	13.49'

Liber 5RC, Page 226. This Corner Certificate is filed in error because of the double corner one chain East of the Corner common to Sections 31 and 32 as stated in the GLO notes.

No date given. The Maas triangulation coordinates sheet obtained from Cleveland Cliffs indicate the Northwest Corner of Section 5 as 0.0 North, 0.0 East, the origin of the CCI coordinate system.

*Handwritten:*  
K  
# 6  
9  
8