

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-518

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:58

For corners in **COMMISSION**

Patricia A. Monley
REGISTER OF DEEDS

MARQUETTE <small>(County)</small>	Located In:	Corner Code E1
1. Public Land Survey	T <u>47N</u> R <u>26W</u>	<u>E1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **1** PAGE **184**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: Section Corner common to Sections 4 and 5, T47N-R26W. 1962: Survey drawing by Walter H. Knapp, Milwaukee for Cleveland Cliffs and recorded in Liber 248, Page 482 indicates Northeast Corner of Section 5 as 18.15' East of the centerline of the railroad. No corner accessories given.

1845: Sam Hill's original survey notes described a corner monument as a wood post 37 l East of the Corner common to Sections 32 and 33, T48N-R26W, referenced by:

8" Birch, S38E, 36 l
Cedar, S64W, 21 l

No date given: Maas Triangulation Coordinates give Northeast Corner of Section 5 as S2.98 and 5299.12E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted a 1 1/2" iron pipe on R.R. grade. Distance West is 2620.87' and distance East is 2633.47'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**
Larry J. Bussone
DATE Dec 6, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced a 1 1/2" diameter iron pipe with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

6" White Birch S56E 107.81 ft.
9" White Pine S74E 114.15 ft.
6" Jack Pine N52E 142.26 ft.
5" White Spruce N42W 36.12 ft.
Steel sign post S60E 1.91 ft.

Monument is located on the Southerly slope of an active R.R. grade and is set flush with the ground.
Bk. 9, Pg. 18



Signed by Gerald W. Carlson

Date 12-28-94

Surveyor's Michigan License No. 24589