

**SURVEY &  
REMONUMENTATION**

APR 28 1995

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 28 PM 5:58

JOB NUMBER: 94030  
SHEET NO. : 1-520

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Patricia A. Monaghan*  
REGISTER OF DEEDS

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>26W</u>	<u>F1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **1** PAGE **186**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Friday, December 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

F1: North 1/4 Corner Section 4, T47N-R26W. Not part of original survey.  
No date given: Marquette County Road Commission, F.B. 755, indicates the North 1/4 Corner of Section 4 as an iron rail.  
No corner accessories given.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Corner position established equidistant between the Northwest and Northeast Corners of Section 4 and on line between the South 1/4 and Southeast Corners of Section 33, T48N-R26W. Distances West and East are 2633.47'. The South 1/4 Corner of Section 33 is West 28.33'.

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**

*Larry J. Bussone*  
DATE Dec 6, 1994

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Set a 10' long 3/4" iron capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 7" Balsam S28E 78.32 ft.
- 8" Maple S06E 101.24 ft.
- 3 1/2" Maple S11W 136.63 ft.
- 12" Cedar S15W 156.01 ft.

Monument is in flooded area.

Bk. 5, Pg. 121

Signed by *Gerald W. Carlson*

Date 12-22-94

Surveyor's Michigan License No. 24589

