

**SURVEY &  
REMONUMENTATION**

APR 28 1995

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 28 PM 5:58

**LAND CORNER RECORDATION CERTIFICATE  
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

*Patricia D. Hanley*  
REGISTER OF DEEDS

LIBER 1 PAGE 188  
Register of Deeds Stamp & File Number

JOB NUMBER: 94030  
SHEET NO. : 1-522

For corners in

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>26W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

GERALD W. CARLSON, in a field survey on Wednesday, December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

G-1: Section Corner common to Sections 3 and 4, T47N-R26W. 1932: Marquette County Road Commission field notes book 1845: Sam Hill's original survey notes describe the corner 451, indicate a Northeast Corner of Section 4 as an iron monument as a wood post set 48.5 l East of the Section pin 1-1/2" diameter on side of 3" strap iron. No corner accessories given. Corner common to Sections 33 and 34, T48N-R26W and referenced by: (See reverse side)  
6" Fir, S10E, 37 l  
Sugar, S40W, 28 l

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Corner position established at GLO offset 33.07' East of the Southwest Corner of Section 34 and on line between the Southwest and Southeast Corners of Section 34, T48N-R26W. Distance West is 2633.47' and distance East is 2634.08'.

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**

*Larry J. Burson*  
DATE Dec 6, 1994

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
7" Maple N19E 25.30 ft.  
10" White Birch S52E 3.42 ft.  
8" White Birch S35W 9.45 ft.  
8" White Birch N62W 3.64 ft.  
Steel sign post S06W 2.36 ft.  
Monument is 0.3' above ground.  
Bk. 6, Pg. 153



Signed by Gerald W. Carlson

Date 12-28-94

Surveyor's Michigan License No. 24589

Record No. 522:

Part "A" Continued:

1969: Land Corner Record filed by Ray J. Brotherton, describes the Corner common to Sections 33 and 34, T48N-R26W and Sections 3 and 4, T47N-R26W as a 1-1/4" old round iron bar at the corner, referenced by:

6" Sugar,	az. 212-1/2,	11.6'
9" Sugar,	az. 313,	9.7'

This record filed in both Townships is in error because the original notes state that there is a double corner at this location.

*Lat. 67  
Dec 20  
Ray J. Brotherton*