

SURVEY & REMONUMENTATION

APR 28 1995

JOB NUMBER: 94030
SHEET NO. : 1-528

LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:58

For corners in

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>26W</u>	J-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Patricia A. Manley
REGISTER OF DEEDS

LIBER 1 PAGE 194
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1: North 1/4 Corner Section 2, T47N-R26W.
Not part of original survey.
1812: County surveyed by Charles Cummings indicates the North 1/4 Corner Section 2, set prorated between the Northeast and Northwest Corners of Section 2, distances East and West 2638.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: The corner position established equidistant between the NW and NE Corners of Section 2 on line between the SW and SE Corners of Section 35, T48N-R26W. Distances West and East are 2610.36'. South 1/4 corner of Section 35, T48N-R26W is East 14.19'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
Power Pole with 2 guy wires N25W 161.67 ft.
First light pole East of building N61E 185.47 ft.
Chiseled 'x' in conc. foundation of building at Southwest corner N05W 192.55 ft.
Punch mark 'x' in steel plate siding of building at Southeast corner N31E 117.03 ft.
Steel sign post North 1.0 ft.
Monument is set on a 7' high flat spoils pile South of and across the road from an abandoned mine building.
Bk. 6, Pg. 117

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussone
DATE Nov 7, 1994

Signed by Gerald W. Carlson Date 12-22-94

Surveyor's Michigan License No. 24589

