

SURVEY & REMONUMENTATION

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-529

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:58

For corners in **COMMISSION**

Patricia S. Minkley
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>26W</u>	<u>K1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **1** PAGE **195**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, November 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1: Section Corner common to Sections 1 and 2, T47N-R26W. This bearing tree Easterly had to be for the Section Corner Sam Hill's original notes describe the Corner monument common to Sections 35 and 36, T48N-R26W as this is the only as a wood post 58 1 West of the Section Corner common Corner of the two that had a bearing tree set to the East to Sections 35 and 36, T48N-R26W, referenced by: (10" Cedar, N84E, 25 1).

12" Cedar, S15E, 10 1
14" Fir, S15W, 13 1

1912: County Survey by Charles Cummings indicates Northeast Corner of Section 2 verified by bearing tree Easterly with a distance West of 2638 to a prorated North 1/4 Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: The 5/8" iron as referenced in part "A" above was discovered to have been erroneously set in the 1993 Carlson survey. A transposition of numbers was discovered and the 1993 iron was inadvertently placed N28-25'E, 9.00' from its calculated position. A Marquette County Survey Monument was placed at the correct position 38.28' West of the Standard Corner to Sections 35 and 36, T48N-R26W.
Distance West is 2610.36' and distance East is 2654.55'. Section Corner common to Sections 35 and 36, T48N-R26W is East 38.28'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Buesome
DATE Nov 7, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

6" Poplar N44W 19.64 ft. Carlson NBT
7" Poplar S66E 17.99 ft. Carlson NBT
4" White Birch S19E 3.86 ft. Carlson NBT
10" Poplar N67W 21.96 ft. Carlson NBT
Steel sign post North 1.0 ft.
Monument is 0.2' above ground and is +/- 110' South of old railroad grade.
Bk. 7, Pg. 139



Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589

Record No. 529:

Part "A" Continued:

1993: Land Corner Recordation Certificate filed by Gerald W. Carlson, PS #24589 set a 5/8 rod with IIs cap #24589 from position noted in CCI notes and coordinates for the Corner with offset of 58 I (38.28') West of CCI position for Corner(K-13) SE Corner of Section 35, T48N-R26W along Township line and on line between SW Corner of SE Corner of Section 35, T48N-R26W. Referenced by:

7" Poplar,	S35E,	18.80'
4" White Birch,	S17W,	11.67'
12" Poplar,	S89W,	25.26'
6" Poplar,	N73W,	19.57'

Handwritten notes:
K-13
900
300
300