## SURVEY & REMONUMENTATION

MARQUETTE COUNTY	1
Fichigan	
RECEIVED FOR RECE	:

JOB NUMBER: 94030

APR 2 8 1995

## LAND CORNER RECORDATION CERTIFICATE Eiling Requirement of Act 74 Mich DA 1970

1994 DEC 28 PM 5: 59

Sheer	NO.	:	1-55.

			rentent of Act 74, wich. F.	A. 1970
For corners in	COMMIS	SSION		Deter alas
MARQUETT (County	E	Located In:	Corner Code ##	Parthering Menlay &
1. Public Land S	Gurvey	T 47N R 26W T R T R T R	L-1	
2. Property Cont in Section	_	T Ŕ		LIBER $1$ PAGE $198$
<ol><li>Miscellaneous Property in Se</li></ol>				Register of Deeds Stamp & File Number
GERALD W. CAR	LLSON , in a f	ield survey on <del>Thursd</del>	lay, December 15 , 19 94	4 7 8 9 10 -11 12
in lines 1 and 2 about current manual of s Management or by a	ove were in confor urvey instructions a decree of a Court of	mance with regulations a of the United States Depa of Law and/or that the corr	A. of 1970, the corner points menti and rules therefore as required it artment of the Interior, Bureau of her points mentioned in lines 3, 4 a f of Land Surveyors or by a Decre	n the Land 7 and 5 8 19 20 21 22 23 24
Court of Law; esta expressed below:	ablished, re-estab	lished, monumented, re	-monumented, recovered, foun	10 30 29 28 27 26 25
	e than 4 corners, ertificate.	all in the same town :	and range, may be recorded	11 12 31 32 33 34 35 36
				10 h

A. Description of original monument and accessories and/or subsequent restoration:

L-1: North 1/4 Corner Section 1, T47N-R26W. Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: The corner position calculated equidistant between the NW and NE Corners of Section 1 on line between the South 1/4 Corner and the SW Corner of Section 36, T48N-R26W. Distances West and East are 2654.55'. The South 1/4 Corner of Section 36, T48N-R26W is East 16.58'.

> RATIFIED BY PEER GROUP P.A. 345 OF 1990

Larry of Bussel DATE Dec 19 1994

•C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

6" Oak

N13W 36.17 ft.

Oak S71E 23.31 ft.

White Birch S35E 13.77 ft.

8" White Birch S88W 17.18 ft.

Steel sign post North 1.97 ft.

Monument is 0.5' above ground.

Bk. 6, Pg. 143

Gerald W Carlson 24589 Burveyor's Michigan License No. \_

Date .

GERALD W. CARLSON **SURVEYOR** No. 24589

AU OFFIAND FURNITURE JAN. 28, 1971 FORM APPROVED BY MICHIGAN STATE

REVISED JAN., 1983