

JOB NUMBER: 95053 SHEET NO.: 1-617

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE (County)

COMMISSION

Located In:

Corner Code #

1. Public Land Survey

47N 26W T47N R26W

M-2 A-2

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Section

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Patricia A. Mearns REGISTER OF DEEDS

LIBER 1 PAGE 235

Register of Deeds Stamp & File Number

GERALD W. CARLSON

Wednesday, August 23 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-2: Quarter Corner common to Section 1, T47N-R26W and Section 6, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 24" Hemlock S82W, 13 l 15" Cedar N81E, 26 l No Date: The corner is indicated on an easement map for Northern Natural Gas Company. No accessories given.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a Magic Marker "X" on rock as set single proportionally on line between the SE and NE Corners of Section 1 by Gerald W. Carlson in 1988. Distance North is 2457.25', and Distance South is 2627.93'.

RATIFIED BY PEER GROUP P.A. 845 OF 1990

Larry J. Busson DATE 10/6/95

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found Magic Marker "X" with a 3/8" X 8" rebar, drilled and grouted in rock, and capped with a 3 1/4" aluminum tablet Marquette County Survey Monument, 0.15' above surface, and stamped to identify the corner. Referenced by nails in existing G. Carlson Bearing Trees:

- 12" Cedar N38W, 21.66' (Carlson N.B.T.) 15" Cedar N53E, 15.22' (Carlson N.B.T.) 15" Hemlock S59E, 23.14' (Carlson N.B.T.) 15" Maple S04W, 17.04' (Carlson N.B.T.) Green Steel Sign Post w/Survey Marker Sign S46W, 1.83'

Bk. 10, pp. 5-6.



Signed by Gerald W. Carlson

Date 12-15-95

Surveyor's Michigan License No. 24589

Grid table with columns A-L and rows 1-13. Cell (2,6) contains '6', (2,5) contains '5', (2,4) contains '4', (2,3) contains '3', (2,2) contains '2', (2,1) contains '1'.