

1995 DEC 27 AM 7:44

JOB NUMBER: 95053 SHEET NO.: 1-620

APR 01 1996 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Located In:

Corner Code #

MARQUETTE (County)

Patricia A. Manley REGISTER OF DEEDS

Table with 3 columns: Description, T/R coordinates, and Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

LIBER 1 PAGE 238

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat Private Claims

Grid table with columns A-L and rows 2-13, containing numerical values for recording purposes.

I, GERALD W. CARLSON, in a field survey on Thursday, November 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5: Section Corner common to Sections 12 and 13, T47N-R26W unknown surveyor, presumably from original B.T.'s. One and Sections 7 and 18, T47N-R25W. 1844: William A. Burt's probable B.T. in place, poor condition. Referenced by: original survey notes describe the corner monument as a 14" Y. Birch S80W, 19.14' 8" Cedar N75E, 32.34' wood post referenced by: Recorded by Dean C. De La Mater RLS #C5778. 8" Y. Birch S35W, 27 l 1951: MCRC P.B. #651 (No page given) indicates the corner and references as recorded above in Record of Surveys Book 1951: A Land Corner Record in Record of Surveys Book #1, Pg. #1, Pg. 57. 57, recorded by the Michigan Department of Conservation 1989: The corner is indicated on two Easement Description Forestry Division, indicates the corner as a set 1" pipe with Maps recorded by Sundberg, Carlson, and Associates in L. 4" Brass Cap. Corner had been placed previous to 1927 by 130, MR Pages 755 & 756, No accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1 1/4" galvanized pipe with 4" dia. brass cap, 1.47' above ground. Also found a 3/4" dia. iron pipe with threaded elbow, S27W, 0.69' from monument, and an old, broken, and squared wood post lying next to existing corner. Line call (1.0 ch. North Enter Swamp) measured @ +/- 70'. Line call (6.0 ch. North Leave Swamp [396']) measured @ +/- 395'. Distance North is 5254.76', and Distance South is 5254.01'.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Lang J. Busane DATE 11/6/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table listing monument details: 20" Y. Birch Stump w/Scribed Butt Blaze S83.5W, 19.05' (Face) (M.D.O.C. N.B.T.), 11" Cedar S89E, 32.50' (Face), 9" Balsam N66W, 2.88' (Face), 11" Maple N07E, 8.60' (Face). Also lists established new references with duplex nails set in: 10" Balsam N65W, 3.23', 7" Balsam N02W, 22.56', 12" Balsam S20E, 33.14', 10" Balsam S02W, 24.83', Green Steel Sign Post w/Survey Marker Sign N00E, 1.0'.



Note: New B.T.'s were face and butt blazed, painted, with B.T. Tags affixed.

Signed by Gerald W. Carlson

Date 12-15-95

Surveyor's Michigan License No. 24589