

1995 DEC 27 AM 7:44

Patricia A. Mansley REGISTER OF DEEDS

JOB NUMBER: 95053 SHEET NO.: 1-624

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Located In:

Corner Code #

MARQUETTE (County)

Table with 3 columns: Description, Survey/Range, and Corner Code. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

18CR 1 PAGE 242 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat Private Claims

Grid table with columns A-L and rows 2-13, containing numbers 6 through 36.

GERALD W. CARLSON, in a field survey on Tuesday, November 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9: Section Corner common to Sections 24 and 25, T47N-R26W unknown surveyor. Corner checked proportionally in all and Sections 19 and 30, T47N-R25W. 1844: William A. Burt's directions. No original evidence of corner found in burned original survey notes describe the corner monument as a wood over plains. Replaced corner with 1" pipe with 4" brass post referenced by: cap. Established reference: 10" Fir N82W, 19 1 8" J. Pine S88E, 89.76' 12" W. Birch S22E, 30 1 1951: MCRS F.B. #651 (No page given) indicates the corner recorded above in Record of Surveys Book #1, Pg. 135. 1951: A Land Corner Record recorded by the Michigan Department of Conservation Forestry Division (Dean C. De La Mater 1989: The corner is indicated on an Easement Description RLS #05778), in Record of Surveys Book #1, Pg. 135, indicates a found 1" bar at corner location previously set by an and Associates in L. 130, MR Pg. 756. Map for Wisconsin Electric recorded by Sundberg, Carlson,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and rejected a 3/4" diameter iron rod, 3" above ground. Distance North is 2637.19', and Distance South is 2654.27'. This position was established using the D.N.R. 1951 survey notes indicating the D.N.R. chainage on their random line between the E-W Railroad spur and the C&NW main track that bears N38W +/- . The chainage on their random line between the tracks was re-created and the corner was set 40.26' East of this random line and 745.80' North of the Southerly Railroad Spur. The D.N.R. indicated that they found an iron at this position in 1951.

RATIFIED BY PEER GROUP P.A. 845 OF 1990

Larry J. Busse DATE 11/13/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" aluminum tablet Marquette County Survey Monument, 0.20' above ground, and stamped to identify the corner. Referenced by duplex nails set in: 5" J. Pine N87E, 89.35' 21" J. Pine S01W, 171.61' 4" J. Pine S22W, 116.15' 8" J. Pine S33W, 84.32' Green Steel Fence Post w/Yellow Survey Marker Sign North, 1.0' Note: Bearing Trees were face and butt blazed, painted, with E.T. Tags affixed. Bk. 9, pp. 53-54. Bk. 11, pp. 65-66.



Signed by Gerald W. Carlson

Date 12-15-95

Surveyor's Michigan License No. 24589