

JOB NUMBER: 95053
SHEET NO. : 1-625

APR 01 1998

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
MARQUETTE COUNTY
1995 DEC 27 10:45
RECEIVED FOR RECORD

1998 DEC 27 10:45
REGISTER OF DEEDS
Patricia L. M...
REGISTER OF DEEDS

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T^{47N} R^{26W} M-10 ✓
T^{47N} R^{25W} A-10
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Section S T R
S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LIBER 1 PAGE 243
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Tuesday, November 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10: Quarter Corner common to Section 25, T47N-R26W and Section 30, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
4" S. Pine S15E, 10 1
3" S. Pine N36W, 5 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Searched, and no subsequent evidence or corner was found. Corner position established by single proportion measurement on line between the S.E. and N.E. Corners of Section 25. Distance North is 2654.27', and Distance South is 2654.27'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Buosoni
DATE 11/6/95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument, 2" above ground, and stamped to identify the corner. Referenced by double headed nails set in:

- 7" J. Pine S41W, 36.41'
- 8" J. Pine N64W, 36.17'
- 7" J. Pine N40E, 48.75'
- 5" J. Pine N79E, 31.57'
- Green Steel Sign Post w/Yellow Survey Marker Sign West, 1.0'

Note: Bearing trees were face and butt blazed, painted, and had bearing tree tags affixed. Corner falls 50.7' West of C/L of 2-track road.

Bk. 9, pp. 69-70.

Signed by Gerald W. Carlson

Date 12-15-95

Surveyor's Michigan License No. 24589