

JOB NUMBER: 95053  
SHEET NO. : 1-626

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

*Thomas A. Handberg*  
REGISTER OF DEEDS

MARQUETTE COUNTY  
RECEIVED FOR RECORD  
1995 DEC 27 AM 7:45

For corners in

MARQUETTE  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 26W

M-11 ✓

T 47N R 25W

A-11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1 PAGE 244  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, November 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11: Section Corner common to Sections 25 and 36, T47N-R26W original evidence was found in burned over plains. Established references:  
and Sections 30 and 31, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:  
6" J. Pine N80W, 5.94'  
5" S. Pine N48E, 34 l 6" J. Pine N44E, 5.94'  
3" S. Pine S80W, 7 l 6" J. Pine S75E, 9.90'  
1951: MCRC F.E. #651 (No page given) indicates the corner and references as recorded above in Record of Surveys Book #1, Pg. 133.  
1951: A Land Corner Record recorded by the Michigan Department of Conservation Forestry Division (Dean C. De La Mater RLS #05778), in Record of Surveys Book #1, Pg. 133, indicates the corner as a set 1" pipe with 4" brass cap. No

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1" hexagonal shaped drill rod, 0.2' below ground. Searched for 1" pipe and 4" brass cap as per 1951 Michigan Department of Conservation notes, but did not find. Distance North is 2654.27'. The remains of a Jack Pine stump were recovered at N80W, 5.94' from the found drill rod indicating that it was probably placed in the position that the D.N.R. pipe and brass cap was placed in 1951. The two S.E.'LY D.N.R. N.B.T.'s were destroyed by the road building activities when the road was built that runs North and South just East of the corner.

RATIFIED BY PEER GROUP  
P.A. 245 OF 1990

*Larry J. Bussone*  
DATE 11/6/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found 1" Hex. drill rod with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" aluminum tablet Marquette County Survey Monument, 0.2' below ground, and stamped to identify the corner. Referenced by found duplex nails in found witness trees:  
7" J. Pine S49W, 36.90'  
13" J. Pine S84W, 24.23'  
8" J. Pine N05W, 37.87'  
7" Forked J. Pine S49E, 75.43'  
Set Green Steel Sign Post w/Yellow Survey Marker Sign West, 1.0'  
Note: Butt blazes and paint were added to existing witnesses previously face blazed with duplex nails  
Bk. 11, pp. 67-68.



Signed by Gerald W. Carlson

Date 12-15-95

Surveyor's Michigan License No. 24589