

1993

COMMISSION

JOB NUMBER: 93300  
SHEET NO. : 1-396  
For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE  
(County)

Located In:

Corner Code #

- 1. Public Land Survey
 

T 47N	R 27W	A-1
T 48N	R 27W	A-13
T 48N	R 28W	M-13
T 47N	R 28W	M-1
- 2. Property Controlling in Section
 

S	T	R	
S	T	R	
- 3. Miscellaneous Property in Sec.
 

S	T	R	
S	T	R	

MARQUETTE COUNTY  
 RECEIVED FOR RECORD  
 1993 DEC 30 PM 1:10  
 1 PAGE 103  
 Register of Deeds Stamp & File Number

LIBER

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on Wednesday, December 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-1: Section Corner common to Section 6, T47N-R27W; Section 1, T47N-R28W; Section 36, T48N-R28W; and Section 31, T48N-R27W. 1846: Austin Burt's original survey notes describe the corner monument as a wood post referenced by:  
 12" Sugar S30.5W, 19 l  
 10" Fir N10.5E, 32 l

1940 - Cleveland Cliffs Iron Company North Lake coordinates indicate the corner as S0.0, E0.0. No description of the corner monument or corner accessories were given. C.C.I. aerial coordintaes N251.61, W36807.63 iron pin S of R.R. grade.  
 1987 - Alan Pierce found an apparent Cummings corner, a 1" iron pin, bent over after being bit by dozer during 1986 forest fire control efforts.  
 (See reverse side).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found concrete monument as described in Allen Pierce's witnesses of 1987, replaced with a Marquette County Survey Monument. Distance East is 2652.22' (1.52' shorter than C.C.I. North Lake distance). and distance South is 7805.70 (3.29' shorter than C.C.I. North Lake distance). The angle checks to within 00 01' 03" from the C.C.I. North Lake angle. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing concrete monument with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 9" Spruce S10E 12.79 ft. Pierce NBT
- 10" Jack Pine S64W 73.00 ft.
- 9" Spruce N68W 179.14 ft.
- 13" Spruce N31W 94.88 ft.

Monument is 0.45 ft. above ground, and lies approximately 20 ft. South of an abandoned railroad grade. 3 Jack Pine Pierce NBT's were found dead.

Bk. 5, Pg. 34



Signed by Gerald W. Carlson Date 12-30-93

Surveyor's Michigan License No. 24589

Record No. 396

Part "A" Continued:

Corner was witnessed by:

9" Spruce	S16E	12.86 ft.
10" Jack Pine	N90W	66.44 ft.

and lies approximately 20 ft. South abandoned C&NW railroad road bed.

Attempts to attain C & NW R/W maps met with no response. Corner position accepted upon verification of calculated section of dimensions and was replaced with a 4" square by 36" long concrete monument embedded with a 1/2" rebar and capped with an orange plastic cap stamped "ECI-30097". Bent pin was buried along side the new monument.

Referenced by:

Recovered witnesses:

9" Spruce	S16°E	12.86 ft.
10" Jack Pine	N09°W	66.44 ft.

New witnesses:

6" Jack Pine	S86°W	33.95 ft.
9" Jack Pine	S89°W	154.55 ft.

Bearing trees are face, nail, butt blazed and painted with distances being measured from a nail in the side of the tree. Butt blaze is scribed as "BT". L5 R.C., Pg. 136

*PK  
#9,000  
V, 1,000  
B...*