

1993

JOB NUMBER: 93300
SHEET NO. : 1-397

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 27W
T 47N R 28W
T _____ R _____
T _____ R _____

A-2 ✓
M-2

2. Property Controlling in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 1 PAGE 97
Register of Deeds Stamp & File Number

1993 DEC 30 PM 1:10
MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

I, GERALD W. CARLSON, in a field survey on Tuesday, December 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2: Quarter Corner common to Section 6, T47N-R27W and 1940 - Cleveland Cliffs Iron Company North Lake Section 1, T47N-R28W. 1846: Austin Burt's original survey coordinate system indicates the coordinates for the corner notes describe the corner monument as a Sugar post as S2528.21, E5.56. No description of the monument or corner accessories were given. 6" Fir S46W, 15 1 No date given - Road Commission Field Book 730 indicates a 3" pipe 3' above ground for the corner. 14" Sugar N70E, 22 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - found a 3" diameter iron pipe filled with concrete 2.8 ft. tall for the West 1/4 corner of Section 6, T47N-R27W. The 3" diameter iron pipe was tied in and proved to be incorrect (71' +/- too far South). The corner was set by proportional bearing and distance between the West 1/4 corner of Section 7 and the Northwest corner of Section 6 based on the C.C.I. North Lake coordinate system. The distance North is 1.07 ft. short and the distance South is 1.11 ft. short of the C.C.I. distances and the angle at the 1/4 corner matches the C.C.I. North Lake angle exactly. Set 5.0' long x 3/4" diameter rebar and a 3 1/4" diameter aluminum tablet Marquette County Survey Monument in South side of old ore pile. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 3/4" diameter x 5.0 ft. long rebar capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
10" White Pine S61E 58.68 ft.
9" White Pine S37E 35.32 ft.
12" Spruce S13E 74.51 ft.
6" Spruce S51W 55.98 ft.
Monument is 0.15 ft. above grade and is located on the South slope of a steep ore stock pile 8 ft. from crest of the pile. No possible NBT's exist in the Northerly direction.
Bk. 5, Pg. 32



Signed by Gerald W. Carlson Date 12-29-93

Surveyor's Michigan License No. 24589