

1993

JOB NUMBER: 93300
SHEET NO. : 1-398

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 27W
T 47N R 28W
T R
T R

A-3
M-3

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 30 PM 1:10
LIBER 1 PAGE 98
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, December 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3: Section Corner common to Sections 6 and 7, T47N-R27W 1940 - Cleveland Cliffs Iron Company North Lake and Sections 1 and 12, T47N-R28W. 1846: Austin Burt's coordinate system indicates the coordinates for the corner original survey notes describe the corner monument as a as S5168.53, E3.64 no description of the monument or corner Maple post referenced by: accessores were given. C.C.I. aerial photo coordinates 12" Fir S45W, 7 l indicate a mushroom (gone) coordinates S4916.11, W36809.17. 10" Fir N11E, 30 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Construction activity in the West Marquette County Landfill destroyed the corner. Resest a Marquette County Survey Monument from C.C.I. North Lake coordinate survey information. The corner was set by proportional bearing and distance between the West 1/4 corner of Section 7 and the Northwest corner of Section 6 based on the C.C.I. Co. North Lake coordinate system. The distance North and South is 1.11 ft. short of the C.C.I. distances and the angle at the Section Corner matches the C.C.I. North Lake angle exactly. Set a Marquette County Survey Monument. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
9" Jack Pine N48E 356.96 ft.
11" Jack Pine N04W 386.55 ft.
11" Jack Pine S36E 421.59 ft.
6" Spruce S86W 312.89 ft.
Monument is 0.45 ft. above grade, 6.5 ft. high steel fence post S61W 2.0 ft.
Monument is 115 ft. East of the North/South fence line.
Bk. 5, Pg. 30



Signed by Gerald W. Carlson
24589

Date 12-29-93

Surveyor's Michigan License No. _____