

1993

JOB NUMBER: 93300
SHEET NO. : 1-399
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 1993 DEC 29 AM 10:43
 REGISTER OF DEEDS
 MARQUETTE COUNTY
 MICHIGAN

	Located In:	Corner Code ##
1. Public Land Survey	T 47N R 27W	A-4 ✓
	T 47N R 28W	M-4
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 1 PAGE 69
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4: Quarter Corner common to Section 7, T47N-R27W and Section 12, T47N-R28W. 1846; Austin Burt's original survey coordinates indicate the corner as S7808.94 W17.93. No notes describe the corner monument as 24" W.Pine. Corner not referenced.

1940 - Cleveland Cliffs Iron Company North Lake description of the corner or corner accessories were given. C.C.I. aerial coordinates - mushroom in road S7554.85, W36833.69.

1980 - C.F. Clark found a 12" cast iron mushroom flush with US-41/M-28 pavement 9.0 ft. South of constructed centerline. (See reverse side).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found MDOT tag and PK nail in East bound lane of US-41 over West 1/4 corner of Section 7. Also found the drill rod and 2 concrete monuments referred to in Brian Taavola's 1987 witnesses. Did not dig up the iron mushroom due to the newly constructed pavement of US-41/M-28 highway. Left the corner as found. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found P-k nail with MDOT reference point tag in the East bound lane of US-41 referenced by nails in:

- 5" Spruce N29E 75.19 ft.
- 7" Red Pine N30W 71.02 ft.

Additional references:

- 4" concrete MDOT state highway marker with aluminum disc N06E 82.13 ft.
- 1" Drill Rod N06E 63.66 ft.
- 4" Concrete Monument state highway marker S06W 77.28 ft.

Stamped MCR 1993 in both MDOT concrete state highway markers.
Bk. 5, Pg.18 (See reverse side for MDOT sketch).



Signed by Gerald W. Carlson

Date 12-28-93

Surveyor's Michigan License No. 24589

Record No. 399

11/19/00
7:00 AM

Part "A" Continued:

Referenced by:

Steel Sign Post South 18.7 ft.

PK nails in:

5" Spruce	S20°W	35.95 ft.
3" Spruce	S35°E	39.74 ft.
5" Norway	N40°W	71.44 ft.

L1 R.C., Pg. 398

1987 - Brian Taavola found a 1' diameter disk which was set by C.P. Cummings. 9.1 ft. South of the centerline of US-41.

Referenced by:

4" Concrete monument	S05° 59' 45" W	77.28 ft.
1" Drill Rod	N05° 59' 45" E	63.66 ft.
4" Concrete monument	N05° 59' 45" E	82.13 ft.

MDOT Traverse Station 52-27
(3/4" pipe with yellow plastic cap S78° 28' 50" W 356.14 ft.)

MDOT Traverse Station 52-28
(3/4" pipe with yellow plastic cap N89° 15' 03" E, 2678.86 ft.)

L5 R.C., Pg. 140

