

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-402
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORDING
1993 DEC 29 AM 10:44
REGISTERED AT 10:00 AM

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 27W	A-7
	T 47N R 28W	M-7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 1 PAGE 76
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Wednesday, December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-7: Section Corner common to Sections 18 and 19, T47N-R27W and Sections 13 and 24, T47N-R28W. 1846: Austin Burt's original survey notes describe the corner monument as a Cedar post referenced by:

- 7" Y.Birch S33W, 18 1
- 7" Y.Birch N38E, 19 1

No date given - C.C.I. aerial photo coordinates iron mushroom S15412.75, W36851.39.

1983 - C.P. Clark found a 12" diameter iron casting with raised lettering, 3' above grade referenced by nails and blazes in:

- 6" Balsam N25W 21.92 ft.
- 8" Cedar N50E 16.39 ft.
- 12" Spruce S40E 16.23 ft.
- 6" Cedar S40W 25.85 ft. L4 RC, Pg. 295

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 12" diameter Cummings monument 2 1/2' tall with lettering set by C.P. Cummings Feb. 1897 Cleveland Cliffs SW cor. sec. 18, T47N-R27W. Left Cummings mushroom as found. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found 12" diameter cast iron mushroom set by C.P. Cummings in Feb. 1897 with raised letters to identify the corner referenced by nails in:

- 6" Balsam N26W 21.91 ft.
- 8" Cedar N54E 16.41 ft.
- 11" Spruce S32E 16.22 ft.
- 9" Cedar S50W 25.89 ft.

Mead paper location tag is S63W 5.8 ft.

Monument is approximately 350 ft. NW of a one story house with mailbox "Spencer 54" on County Road 482. Bk. 5, Pg. 10



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589