

1993

JOB NUMBER: 93300

SHEET NO. : 1-403

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 27W	A-8 ✓
	T 47N R 28W	M-8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 29 AM 10:43  
 RECEIVED FOR RECORD  
 MARQUETTE COUNTY  
 MICHIGAN  
 REGISTER OF DEEDS  
 LIBER 1 PAGE 75  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-8: Quarter Corner common to Section 19, T47N-R27W and Section 24, T47N-R28W. 1846: Austin Burt's original survey notes describe the corner monument as a Sugar post referenced by:  
 10" Y. Birch S07W, 15 l  
 10" Fir N65E, 33 l

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 - Found 2" squared cedar post in small pile of rocks with flagged lath 1.0 ft. South. This wood post was an approximate corner set by Larry Bussone, P.S. for some C.C.I. work. Set a Marquette County Survey Monument proportioned on line between the NW and SW corners of Section 19, 37 ft. +/- West of approximate post. Peer group ratification 12-20-93.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
 9" Spruce S54E 14.05 ft.  
 11" Spruce S45W 51.27 ft.  
 5" Spruce N90W 34.18 ft.  
 7" Maple N07E 4.97 ft.  
 Monument is 0.60 ft. above ground at toe of small rise to the NE.  
 Bk. 5, Pg. 16



Signed by Gerald W. Carlson Date 12-28-93  
 Surveyor's Michigan License No. 24589