

1833

JOB NUMBER: 93300
SHEET NO. : 1-395

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 47N R 27W
T 48N R 27W

B-1
B-13

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MARQUETTE COUNTY
RECEIVED FOR RECORDATION
1993 DEC 30 PM 1:09
LIBER 1 PAGE 96
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Wednesday, December 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1: Quarter Corner common to Section 6, T47N-R27W and 1940 - Cleveland Cliffs Iron Co.'s North Lake coordinates Section 31, T48N-R27W. 1846: Austin Burt's original survey indicate the corner is S4.29, E2653.79. No description of notes describe the corner monument as a Spruce post the monument or corner accessories were given. referenced by:
10" Spruce N67E, 15 l
10" Spruce N47W, 10 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found a piece of railroad rail set vertically in marsh North of the old railroad grade and the East side of a power line right-of-way clearing. Set a 5.0 ft. long 3/4" diameter rebar capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument along side the railroad rail at the corner position. Distance West is 2652.22' (1.52' shorter than C.C.I. North Lake distance) and distance East is 2642.82' (1.63' shorter than C.C.I. North Lake distance). The angle checks to within 00 01' 46" from the C.C.I. North Lake angle. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 3/4" x 5.0 ft. long rebar capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument placed along side the web of the found railroad rail stamped to identify the corner referenced by nails in:
6" Cedar N54E 89.18 ft.
8" Cedar S82E 70.01 ft.
8" Spruce S40E 97.00 ft.
Power Pole S02W 103.31 ft.
Monument is 0.90 ft. above ground, and located directly under an North/South power line with single poles and 107 ft. +/- North of the old railroad grade.
Bk. 5, Pg. 42



Signed by Gerald W. Carlson
24589

Date 12-30-93

Surveyor's Michigan License No. _____