

MAY 22 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
RECEIVED FOR RECORD

1996 NOV 18 PM 2:27

Patricia A. Monney
REGISTER OF DEEDS

For corners in
MARQUETTE
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>47N</u> R <u>27W</u> | <u>C-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

LIBER **1** PAGE **304**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		●		8		9		10		11		12
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on AUGUST 12TH, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4: Quarter Corner common to Sections 7 and 8.

1848: John Burt's original survey notes describe the corner monument as a Cedar wood post referenced by:
20" Sugar N10E, 43 L 30" W. Pine N70W, 33 L

No Date: The corner is indicated on a map of The Seilo Lots, recorded in L. 194, Deeds Pg. 52, as being at the centerline of County Road G.J.. No accessories given.

No Date: M.C.R.C. Field Notes (no F.B. # given) indicate the corner as a 3/4" Bolt 10" below the surface in the center of a road. No accessories given.

No Date: A map by Ray A. Brotherton P.E. #47, recorded in L. 201, Deeds Pg. 7, indicates the corner at the center of a road. Distance North, 2583.2' to the N.W. Corner of Section 8. Distance East, 2697.44' to the Center 1/4 Corner of Section 8. No description of corner object or accessories given.

1970: The corner is indicated on a revision of the map shown above, as revised by R.J. Brotherton in 1970, and recorded in L. 280, Deeds Pg. 247. The corner is shown at the center of County Road G.J.. No accessories given.
(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4: 1996: No original evidence found. Found and accepted a 1/2" Iron, 0.3' below asphalt surface in a cast iron monument box, +/- 3' West of the C/L of Stoneville Road, and +/- 65' South of the C/L of Randall Road. Did not check line calls as entire area has been altered by man since original survey. Distance North is 2585.19' and Distance South is 2587.87'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4: 1996: Replaced found 1/2" Iron with a 3/4" X 5' long rebar capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.3' below paved surface in found cast iron monument box.

Referenced by:

- | | | |
|--|-------|--------|
| 10" Trip. Maple (D.H. nail only, N. side, 1.5' high) | S87E, | 88.13' |
| N.W. Cor. Block Found. Hse. #100 Stoneville Rd. | S55E, | 82.72' |
| N.E. Cor. Block Found. Hse. #105 Stoneville Rd. | S75W, | 57.34' |
| 4" Square Conc. Mon. (0.6' high, iron @ top) | N79W, | 32.93' |

Note: Did not blaze witness tree or set post and sign due to corner location in residential area.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussome
DATE 10/28/96



Signed by Gerald W. Carlson Date 10-29-96

Surveyor's Michigan License No. 24589