

**SURVEY &
REMONUMENTATION**

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-487

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:56

For corners in

MARQUETTE
(County)

COMMISSION

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>47N</u> R <u>27W</u> | C-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Patricia L. Manley
REGISTER OF DEEDS

LIBER

1 PAGE 158

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Tuesday, December 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| C-13: Section Corner common to Section 5 and 6, T46N-R27W and Sections 31 and 32, T47N-R27W. | 10" Yellow Birch, S73E, 35 l 20" Tamarack, S34, 17 l |
| 1846: Austin Burt's original survey notes describe the Corner monument as a Fir post, referenced by: 6" Spruce, N60-1/2E, 33 l 7" Fir, N86W, 37 l | 1980: A Land Corner Recordation Certificate filed by Charles F. Clark, RLS #25836 indicates he found a 1-1/2" iron pipe 3 feet above grade. Referenced by Nails in: 8" Balsam, S60W, 12.15 3" Spruce, S20E, 8.00 6" Spruce, North 19.08 6" W. Birch, N65W, 15.86' |
| 1848: Harvey Mullen's original subdivision notes for T46N-R27W indicate the following additional references for the Northeast Corner of Section 6, T46N-R27W: | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted 1-1/2" iron pipe as referenced in Part "A" above. Distance West is 2656.21' and distance East is 2650.65'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Buosme
DATE Nov 21, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994 - Replaced 1 1/2" iron pipe with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
- 5" Balsam N88W 31.70 ft.
 - 7" White Birch N72W 16.01 ft. Clark NBT
 - 6" Spruce N12W 30.68 ft.
 - 4" Maple S45E 12.22 ft.
 - Steel sign post N02E 1.41 ft.
- Monument is 0.4' above ground.
Bk. 5, Pg. 129



Signed by Gerald W. Carlson

Date 12-28-94

Surveyor's Michigan License No. 24589