

**SURVEY &
REMONUMENTATION**

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030

LAND CORNER RECORDATION CERTIFICATE

SHEET NO. : 1-488

APR 28 1995

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:56

For corners in

MARQUETTE **COMMISSION**
(County)

Located In:

Corner Code #

- | | | | |
|---------------------------------------|-------|-------|------|
| 1. Public Land Survey | T 47N | R 27W | D-13 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling
in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous
Property in Sec. | S | T | R |
| | S | T | R |

Patricia R. Muley
REGISTER OF DEEDS

LIBER **1** PAGE **159**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13: 1/4 Corner common to Section 5, T46N-R27W and Section 32, T47N-R27W.
1846: Austin Burt's original survey notes describe the Corner monument as a Cedar post referenced by:
10" Maple, N40E, 46 1
7" Maple, N66W, 53 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: The Corner position established at proportional distance and on line between the SW Corner of Section 32 and the Meander Corner West of Long Lake. Distance West is 2650.65' and distance East is 2091.36' to Meander Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
4" Spruce S49W 40.19 ft.
3 1/2" Spruce N05W 22.15 ft.
3 1/2" Spruce N71E 21.92 ft.
4" Spruce N87E 4.27 ft.
Steel sign post N79E 1.26 ft.
Monument is 0.3' above ground.
Bk. 5, Pg. 131

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bassone
DATE Dec. 6, 1994

Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589

