

JOB NUMBER: 95053  
SHEET NO. : 1-636

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

APR 11 1996

MARQUETTE COUNTY  
RECEIVED FOR RECORD  
1995 DEC 27 AM 7:46  
REGISTER OF DEEDS  
*Antoinette M. Hildebrand*

For corners in

MARQUETTE  
(County)

Located in:

Corner Code #

- |                                      |   |     |   |     |     |
|--------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey                | T | 47N | R | 27W | J-3 |
|                                      | T |     | R |     |     |
|                                      | T |     | R |     |     |
|                                      | T |     | R |     |     |
| 2. Property Controlling in Section   | S |     | T |     | R   |
|                                      | S |     | T |     | R   |
| 3. Miscellaneous Property in Section | S |     | T |     | R   |
|                                      | S |     | T |     | R   |

LIBER 1 PAGE 26  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3									●		
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, GERALD W. CARLSON, in a field survey on Tuesday, November 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

J-3: Quarter Corner common to Sections 2 and 11. 1848: John Burt's original survey notes describe the corner monument as a Yellow Birch post referenced by:  
12" Fir S65E, 32 l  
12" Fir S85W, 08 l  
1891: G.P. and Charles Cummings, in Record of Surveys Pg. 205, indicate the corner as previously established. Distance West to SW Corner of Section 2 is 2609.00'; and distance East to SE Corner Section 2 is 2647.50'.  
1892: George Cummings, in Record of Surveys Pg. 227, indicates the corner as 2596.9' North of the Center of Section 11, and 5181.1' North of the South 1/4 Corner of Section 11. 1989: An LCRC recorded by Gerald W. Carlson RLS #24589, in L. 5, RC Pg. 258, indicates the corner as a found 1' diameter CCI iron cap on a 2" pipe, 72' South of old R.R. grade in tagalder swamp. No corner accessories available as the corner is situated in a tagalder swamp.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1995: Found and accepted a 1' diameter cast Cummings tablet on a 2" pipe, 2.3' above ground in tagalder swamp, 3' South from edge of water. Distance East is 2648.89' and Distance West is 2610.86'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1995: Referenced existing Cummings monument using duplex nails set in:  
12" Cherry N89E, 78.59'  
12" W. Pine S21E, 123.30'  
5" Spruce S62W, 97.62'  
8" Maple N32W, 176.63'  
Green Steel Sign Post w/Survey Marker Sign S25E, 1.8'  
Note: Bearing Trees were face and butt blazed, painted, and had B.T. Tags affixed.  
Bk. 11, Pg. 91.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990  
*Larry J. Bussone*  
DATE 11/13/95



Signed by Gerald W. Carlson Date 12-20-95  
Surveyor's Michigan License No. 24589