

1993

COMMISSION

JOB NUMBER: 93300  
SHEET NO. : 1-386

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <sup>47N</sup> R <sup>27W</sup> T <sup>48N</sup> R <sup>27W</sup> T _____ R _____ T _____ R _____	<u>K-1</u> ✓ K-13 _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

LIBER 1 PAGE 93  
Register of Deeds Stamp & File Number

RECEIVED FOR RECORD  
MARQUETTE COUNTY MICHIGAN  
1993 DEC 30 PM 1:09

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Tuesday, December 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-1: Section Corner common to Sections 1 and 2, T47N-R27W 1892 - Cleveland Cliffs Iron Company records and Sections 35 and 36, T48N-R27W. 1846: Austin Burt's original survey notes describe the corner monument as an Ironwood post referenced by:  
 10" W.Birch N51E, 26 1  
 7" W.Birch N68W, 24 1

1892 - Cleveland Cliffs Iron Company records indicate a mushroom set by G.P. Cummings with coordinates N92.81, W10337.22. Maas coord. system indicates the coordinates as N98.77, W10337.64. No monument description or corner accessories given.  
 1949 - MDOT R/W maps indicate the corner as existing. No corner accessories given.  
 1990 - Corner indicated on the assessor's plat of Water St. No corner accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - The corner position was calculated by proportional bearing and distance between the NE corner of Section 1, and the NW corner of Section 2, using the C.C.I. Company's triangulation coordinates. The angles matched exactly and the distance East is 5300.17 ft. (0.20 ft. longer than C.C.I.) and the distance West is 2655.64 ft. (0.10' longer than C.C.I.). A nail in rock with an aerial target cross was found 2 ft. +/- SW of the calculated corner position.  
 Decr group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 5/8" iron capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
 8" White Birch N15W 25.20 ft.  
 10" Poplar N09E 20.12 ft.  
 5" White Birch N39E 33.19 ft.  
 7" Poplar N56E 28.38 ft.  
 Monument is 0.50 ft. above ground.  
 Bk. 4, Pg. 91



Signed by Gerald W. Carlson Date 12-29-93

Surveyor's Michigan License No. 24589