

JOB NUMBER: 95053
SHEET NO. : 1-629

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1995 DEC 27 AM 7:46
REGISTER OF DEEDS
Richard A. Henderson

APR 5 1 1996

For corners in
MARQUETTE
(County)

COMMISSION Located In:

Corner Code #

	47N	27W	K-2
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R

LIBER 1 PAGE 25
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

GERALD W. CARLSON Monday, November 27 95

I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-2: Quarter Corner common to Sections 1 and 2. 1848: John

Burt's original survey notes describe the corner monument as a Sugar post referenced by:

8" Y. Birch N21E (No Distance Given)

9" Maple S39W 15 1

1891: George P. Cummings, in Record of Surveys Pg. 205, indicates the corner as a Tee Rail lying 2623.8' North of the SE Corner and 2528.35' South of the NE Corner of Section 2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 12" diameter cast iron Cummings monument, 0.2' below ground, solid and in very good condition. Distance North is 2530.82' and distance South is 2623.90'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Busone
DATE 11-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Established the following references to the found Cummings monument using duplex nails set in:

6" W. Pine N25E, 3.52'

20" Spruce S38E, 14.94'

12" W. Pine S21W, 42.42'

12" Spruce N81W, 38.45'

Green Fence Post w/ Survey Marker Sign North, 2.0'

Note: Bearing trees were face and butt blazed, painted, and had stamped bearing tree tags affixed

Bk. 11, Pg. 83.



Signed by *Gerald W. Carlson*
24589
Surveyor's Michigan License No. _____

Date 12-20-95