

JOB NUMBER: 95053
SHEET NO. : 1-635

APR 6 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

- | | | |
|--------------------------------------|---|-----------|
| 1. Public Land Survey | T ^{47N} _____ R ^{27W} _____ | K-3 _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Monday, November 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-3: Section Corner common to Sections 1, 2, 11, and 12. cates the corner as previously established. Distance South to SE Corner of Section 11 is 5204.4'.
 1848: John Burt's original survey notes describe the corner monument as a Sugar post referenced by:
 14" Y. Birch N60E, 29 1
 9" Y. Birch S74W, 30 1
 1891: G.P. and Charles Cummings, in Record of Surveys Pg. 205, indicate the corner as having been previously established, and lying 2623.8' South of the East 1/4 Corner, and 2647.50' East from the South 1/4 Corner of Section 2.
 1892: George Cummings, in Record of Surveys Pg. 227, indicates the corner as previously established. Distance South to SE Corner of Section 11 is 5204.4'.
 No Date: An unidentified map recorded in L. 283, Deeds Pg. 562 shows the corner.
 No Date: The corner is shown on an unidentified map recorded in L. 283, Deeds Pg. 574.
 1991: The corner is shown on a map by Larry J. Bussone RLS #25833 recorded in L. 393, Deeds Pg. 223. No accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1' diameter Cummings Iron Mushroom Monument, set in rock and plumb. Distance North is 2623.90', Distance East is 2634.87', and Distance West is 2648.89'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Established references to the found Cummings mushroom monument using duplex nails set in:

- | | | |
|---|-------|--------|
| 16" W. Pine | S71W, | 48.92' |
| 12" Maple | N23W, | 20.52' |
| 10" Maple | N58E, | 51.51' |
| 12" Maple (Fd. old blaze, no nail) | East, | 5.66' |
| 10" Maple | S65W, | 12.85' |
| Green Steel Fence Post w/Survey Marker Sign | N29W, | 3.5' |

Note: Bearing trees were face and butt blazed, painted, and had B.T. Tags affixed.

Bk.11, PP. 83-84.

Signed by Gerald W. Carlson

Date 12-20-95

Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976
REVISED JAN. 1983

REGISTER OF DEEDS
 MARQUETTE COUNTY
 RECEIVED FOR RECORD
 1995 DEC 27 AM 7:47
 G. W. Carlson
 REGISTER OF DEEDS

LIBER 1 PAGE 28
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE 11/13/95

