

JOB NUMBER: 95053

SHEET NO. : 1-634

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1995 DEC 27 AM 7:47  
REGISTER OF DEEDS  
D. H. H. H.

For corners in

MARQUETTE  
(County)

Located In:

Corner Code #

1. Public Land Survey	T 47N	R 27W	L-3
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R

LIBER 1 PAGE 263  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, GERALD W. CARLSON, in a field survey on Wednesday, November 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3: Quarter Corner common to Sections 1 and 12. 1848: John Burt's original survey notes describe the corner monument as a Sugar post referenced by:  
8" Y. Birch S08E, 17 l  
6" Y. Birch N09W, 19 l  
1988: The Assessor's Plat of Jackson Misc. surveyed by Gerald W. Carlson RLS #24589 and recorded in L. 12, Plats pp. 319B - 320B, indicates the corner as a found 1 1/4" pipe. Distance N89-45-48W, 2634.63' to the SW Corner of Section 1.  
No accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 2" O.D. pipe, 3.9' high, in good condition. Distance East is 2648.99' and Distance West is 2634.87'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found 2" pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" aluminum tablet Marquette County Survey Monument, 0.3' above ground, and stamped to identify the corner. Corner lands on a terrace of Spruce, Cedars, Birches, and Poplars. It is also full of outcropping rock. Established references:  
14" Spruce N17E, 10.25'  
7" Cedar N89E, 42.92'  
8" Cedar S70W, 12.52'  
8" Spruce N81W, 43.38'  
Green Steel Sign Post w/Survey Marker Sign North, 2.05' (To Face)  
Bk. 11, PP. 81-82.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Bussme*  
DATE 11/13/95

Signed by *Gerald W. Carlson*

Date 12-20-95

Surveyor's Michigan License No. 24589

