

**SURVEY &
REMONUMENTATION**

JOB NUMBER: 94030
SHEET NO. : 1-509

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PH 5:57

For corners in

APR 28 1995

Patricia A. Monley
REGISTER OF DEEDS

MARQUETTE
(County)

COMMISSION Created In:

Corner Code --#

- | | | |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 47N R 27W | M-3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

LIBER **1** PAGE **175**
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Wednesday, December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| M-3: NE Corner of Section 12. | 9" Sugar N10E 12 1 |
| 1844: William A. Burt's original survey notes describe the corner monument as a post referenced by: | 16" Sugar S65E 08 1 |
| 7" Birch N37W 4 1 | No date given: MAAS coordinates indicate the NE corner of Section 12, T47N-R27W as South 5087.85 and West 4998.79. |
| 20" Sugar S75E 8 1 | |
| 1845: Sam Hill's original subdivision survey notes for T47N-R26W indicate the following additional references for the NW corner of Section 7, T47N-R26W. | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position calculated from early 1900 Maas Mine coordinate values from two found corners 1/2 mile North and South. Distance South is 2640.26' (2640.59' Maas) and distance North is 2618.45' (2618.79' Maas). This corner falls in the side slope of the old Jackson Mine pit.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Benson
DATE Dec 19, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994 - Set a 2 1/2' long 3/4" re-rod capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
- 4" White Birch S76W 17.07 ft.
 - 4" White Birch N75W 23.67 ft.
 - 5" White Birch N54W 22.10 ft.
 - 3" White Birch S76E 33.68 ft.
 - Steel sign post West 1.5 ft.
- Monument is flush with ground, positioned on steep side slope of old mine pit and grouted in place.
Ek. 8, Pg. 65

Signed by Gerald W. Carlson
Surveyor's Michigan License No. 24589

Date 12-28-94

