

**SURVEY &
REMONUMENTATION**

JOB NUMBER: 94030
SHEET NO. : 1-506
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 28 1995

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:57

Patricia D. Monbey
REGISTER OF DEEDS

MARQUETTE (County) **COMMISSION** Located In: _____ Corner Code ## _____

1. Public Land Survey	T 47N	R 27W	M-6
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **1** PAGE **172**
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6: East 1/4 Corner of Section 13, _____ Corner of Section 13, are South 12954.89 and West 4860.01.
1844: William A. Burt's original survey notes describe the corner monument as a post referenced by:
11" Sugar S65W 3 1
16" Sugar S28E 27 1
1913: C.C.I. Company coordinate list indicates the East 1/4 Corner of Section 13, T47N-R27W as an iron pipe with coordinates South 12954.89 and West 4860.01.
No date given: The MAAS coordinates for the East 1/4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted the 1 1/2" iron pipe as referenced above in part "A".
Distance South is 2614.13' and distance North is 2626.20'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussard
DATE Dec 19, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
12" Maple S15W 8.75 ft.
7" Maple N75W 11.82 ft.
12" Maple N23W 28.25 ft.
11" Maple N37E 16.09 ft.
Steel sign post North 4.6 ft.
Found pipe referenced in part "B" above was cut off to 1.0' above ground and capped with the 3 1/4" diameter cap.
Tablet was held secure to the pipe with a 1/4" bolt.

Signed by Gerald W. Carlson
Surveyor's Michigan License No. 24589

Date 12-28-94

