

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~46-47~~ NR ~~28~~ W

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1, 2, 35 and 36.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap. -----

WITNESSES TO CORNER ----- 15" Red Pine N 45 E ----- 14 Links
marked S 36 NBT

----- 13" W. Pine S 51 E ----- 14.5 Links
marked S 1 NBT

----- 8" Soft Maple S 74 W ----- 60 Links
marked S 2 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced as previously set by unknown surveyor. 1" Iron Bolt in place. Corner lies in old fence corner to North and East.

County Road Commission records indicate this corner was in place in 1936.

Found no evidence of original B.T.'s.

Corner used by local residents for many years.

Corner was placed and witnessed 22 April 1958.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 4-15-59
REGISTERED LAND SURVEYOR