

I-4:

PART A CONTINUED:

1987: A Certificate of Survey recorded by Charles F. Clark P.S. #25836 in L. 362, SM Pg. 173, indicates the corner as a Concrete Monument referenced by nails in:

4" Maple	S48E,	22.39'	5" Balsam	S35W,	18.01'
6" Maple	N50W,	25.64'	12" W. Birch	N65E,	22.00'

1987: An LCRC recorded by Charles F. Clark P.S. #25836 in L. 5, RC Pg. 130, indicates the corner noted as fence intersection on MDSHD plans for US-41/M-28 (Project 52-39); noted as fence corner on 1957 survey of parcels in N.E. 1/4 Sec. 10-47-28 by RLS #11369. He found a Concrete Monument at approximate intersection of old (down) fence lines, witnessed by apparent NBTs as described below. Origin of monument/NBTs unknown, but apparently used in prior area surveys; accepted as most probable corner position due to lack of substantial conflicting evidence.

4" concrete monument with 1/2" rod witnessed by:

6" Maple	N50W,	25.64'	(found nail/tag, blazed) (NBT)
12" W. Birch	N65E,	22.00'	(set P.K. nail, blazed) (NBT)
4" Maple	S48E,	22.39'	(set P.K. nail)
5" Balsam	S35W,	18.01'	(set P.K. nail)

1995: A description sketch recorded by Alan K. Pierce P.S. #30097 in L. 403, Deeds Pg. 697, indicates the corner as N00-15'-00"E, 2637.80' from the S.E. Corner of Section 10. No description of corner object or accessories given.

1996: Description Sketches recorded by Alan K. Pierce P.S. #30097 in L. 404, Deeds Pg. 540, and L. 404, Deeds Pg. 543, indicate the corner as N00-15'-00"E from the S.E. Corner of Section 10. No description of corner object or accessories given.

1997: A description sketch recorded by Alan K. Pierce P.S. #30097 in L. 412, Deeds Pg. 820, indicates the corner. No description of corner object or accessories given.

1997: A Certificate of Survey recorded by Alan K. Pierce P.S. #30097 in L. 2, Pg. 299, indicates the corner as a found concrete monument as referenced in L. 5, RC Pg. 130. Distance S00-15'-00"W, 2637.80' to a found 1" pin in concrete at the S.E. Corner of Section 10.