

SECTION 1838

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1998 DEC 29 PM 3:19

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Patricia L. Manley
REGISTER OF DEEDS

For corners in MARQUETTE Located in: _____ Corner Code # _____
(County)

1. Public Land Survey T 47N R 28W _____ K-2
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER **R 2** PAGE **93**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on December 14, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-2: Quarter Corner common to Sections 1 and 2.
1848: This corner was not set in the original 1848 survey. The corner fell in the water of North Lake .

1908: Old CCI company survey notes indicate an iron pin 4' long driven within 6" of surface of water & cemented. Pin is 4' from shore (West) of North Lake in 1' of water. Good gravel bottom. Bearing 10' North of stake squared on one side. North Lake coordinates (CCI) indicate the corner set by single proportionate measurement between the SW and NW corners of Section 1. Distance North is 2531.30' and distance South is 2619.70'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-2: 1998: Found and accepted a 1 1/4" solid iron with a 3 1/2" diameter X 3/4" thick cap 0.80' high and solid. Stamped cap to identify the corner and also "MCR 98" on cap. The corner is now high and dry! This portion of North Lake has been permanently altered by mining company construction. An old swail is approximately 100' to the West. The corner lies in a low area of ground that could have been part of North Lake at the time of the original survey. Distance North is 2530.85' and distance South is 2618.78'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-2: 1998: Found a 1 1/4" solid iron with a 3 1/2" X 3/4" thick cap. Stamped the cap to identify the corner and also "MCR 98" on cap. Monument is 0.80' above ground. Established references:
9" W. Birch N78W 11.51' 5" Balsam N14W 4.21'
6" Balsam S16E 20.69' 5" Maple S06W 13.88'

Green Steel Sign Post w/ Yellow Survey Marker Sign, N75E, 2.4'
Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.
Bk.14 , Pg. 121

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Bussone
DATE 11/9/98



Signed by Gerald W. Carlson Date 12-28-98
Surveyor's Michigan License No. 24589