

1998 DEC 29 PM 3:20

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Patricia R. Monney*  
REGISTER OF DEEDS

For corners in  
MARQUETTE  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 47N R 28W K-5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

LIBER **R 2** PAGE **96**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, GERALD W. CARLSON, in a field survey on JULY 22ND, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5: Corner common to Sections 11, 12, 13, and 14.  
1848: John Burt's original subdivision survey notes describe the corner monument as a Maple post. Top of hill 80' Course E.S.E.. Referenced by:  
8" Sugar S42W, 10 L 16" W. Pine N40E, 16 L

1897: George and Charles Cummings, in Record of Surveys pp. 260-261, indicate the corner as 2619.2' South of the West 1/4 Corner of Section 12; and 2667.35' West of the South 1/4 Corner of Section 12. No description of corner object or accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5: 1998: Found and accepted a 1 1/4" I.D. Iron Pipe, 3.0' above ground, painted white with old flagging. Pipe falls at top of hill bearing E.S.E on Westerly side, and is 5' long with a dead head at the bottom. Found a 5" maple with face blaze and Mead location tag, S49W, 2.72' (to C/L) from fd. Iron Pipe. Also found possible decayed remains (old stump and fallen tree) of Original GLO Witness: 16" W. Pine, N40E, 16 L, at appropriate bearing and distance from corner. Found remains of ancient barbed wire fence running North and East from Corner, with good brush line and blue painted line running East from corner to the South 1/4 Corner of Section 12. Checked Line Call: (Descend Hill and Ledge E.-W., 1.00 chains [66'] North from corner. Measured Call: Taped 56' North to E.-W. ledge on North slope near top of hill. The following calls to the East of corner were originally (GLO) measured on a random line, and we found them to fit best when measured 10 - 15' South of brushed line to east. Checked Line call: (Descend ledge Course E.S.E., 2.50 chains [165'] East from Corner.). Measured call: East, 248' to descent down conspicuous rock ledge Course E.S.E. Checked Line Call: (Foot of Hill and Ledge 80', 12.00 chains [792'] East from Corner). Measured Call: East, 741', to foot of small hill and small rock ledge. Checked Line Call: (Ascend gradually, 13.00 chains [858'] East from Corner). Measured call: East, 792', to point commencing gradual ascent to East. Note: All calls to East were measured with a hip chain. Distance East is 2667.88' and distance West is 2634.61'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5: 1998: Replaced found 1 1/4" I.D. Iron Pipe a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.6' above ground, with a small pile of rocks placed around it. Corner is +/- 430' West of gate at end of two track road. Measured found reference:  
17" R. Pine N49W, 18.11' ( to set d.h. nail - tree had old fd. face blaze)  
Established references:  
16" Trip. Oak N47E, 43.05' ( set d.h. in East-most trunk)  
20" W. Pine S28E, 57.01' 5" Maple S18W, 15.55'  
Green Steel Sign Post w/ Yellow Survey Marker Sign S14E, 2.92'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. , Pg.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Bussone*  
DATE 11/9/98



Signed by Gerald W. Carlson

Date 12-28-98

Surveyor's Michigan License No. 24589