

JOB NUMBER: 93300
SHEET NO. : 1-401
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>47N</u> R <u>27W</u>	<u>A-6</u>	
	T <u>47N</u> R <u>28W</u>	<u>M-6</u> ✓	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORDATION
1993 DEC 29 AM 10:44
REGISTERED
LIBER 1 PAGE 77
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Wednesday, December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>A-6: Quarter Corner common to Section 18, T47N-R27W and Section 13, T47N-R28W. 1846: Austin Burt's original survey notes describe the corner monument as Spruce post referenced by:</p> <p>10" Spruce S56W, 53 l</p> <p>14" Spruce N80E, 17 l</p>	<p>No date given - C.C.I. aerial photo coordinates indicate iron mushroom with coordinates S12692.78, W36827.77. 1983 - C.F. Clark found a 12" diameter iron casting with raised lettering, 2' above grade referenced by nails and blazes in:</p> <p>6" Maple S20W 14.98 ft.</p> <p>7" Cedar S65W 36.19 ft.</p> <p>8" White Birch S10E 27.11 ft.</p> <p>6" Alder N10E 48.38 ft. L4 RC, Pg. 295</p>
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 12" diameter Cummings mushroom at West 1/4 corner of Section 8, T47N-R27W and witnesses per C.F. Clark LCRC L7/83. Left iron mushroom as found. South of old railroad grade found old brush line and blue paint line South of Carp River. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found 12" diameter cast iron mushroom set by C.P. Cummings in Feb. 1897 with raised letters to identify the corner referenced by nails in:

18" Spruce N05E 55.08 ft.

10" White Birch S10E 26.95 ft. Clark NBT

5" Maple S20W 14.99 ft. Clark NBT

9" Cedar S76W 36.22 ft. Clark NBT

Monument is 2.1 ft. above ground in swamp on South side of Carp River and is slightly leaning.

Bk. 5, Pg. 12



Signed by Gerald W. Carlson Date 12-28-93
Surveyor's Michigan License No. 24589