

1983

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-407

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 27W	A-12
	T 47N R 28W	M-12 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1983 DEC 29 AM 10:43

1 PAGE 72

LIBER Register of Deeds Stamp & File Number

*Gerald W. Carlson*  
REGISTERED PROFESSIONAL SURVEYOR

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Tuesday, December 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-12: Quarter Corner common to Section 31, T47N-R27W and Section 36, T47N-R28W. 1846: Austin Burt's original survey notes describe the corner monument as a Cedar post referenced by:  
6" Spruce S60W, 5 1  
(No Species) N35E, 9 1

No date given- Marquette County Road Commission field book #512 indicates a post at a fence intersection.  
No corner accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Set spike in center of old rotted and broken off fence corner post and strands of barbed wire to North and West. The point to this fence post is in good condition. Replaced the corner fence post with a Marquette County Survey Monument. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
4" Black Spruce N66W 29.39 ft.  
10" White Birch N36E 24.53 ft.  
6" Black Spruce N84E 35.15 ft.  
6" Black Spruce S47W 20.12 ft.  
Monument is flush with ground in swampy Spruce woods.  
Bk. 5, Pg. 4



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589