

JOB NUMBER: 93300  
SHEET NO.: 1-408  
For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1993 DEC 29 AM 10:43

*Patricia A. Mackay*  
REGISTER OF DEEDS

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 27W	A-13
	T 47N R 28W	M-13 ✓
	T 46N R 27W	A-1
	T 46N R 28W	M-1
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 71  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on Tuesday, December 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13; Section Corner common to Section 31, T47N-R27W; Section 6, T46N-R27W; Section 1, T46N-R28W; and Section 36, T47N-R28W. 1846: Austin Burt's original survey notes describe the corner monument as an 11" Fir referenced by: 32" W.Pine N22E, 31 1

1936 - Marquette County Road Commission field book #550 indicates the corner as a 3" iron pipe. Measuring Southerly on line 287 ft. to creek, 454 ft. ascend hill, 1043 ft. descend hill, 1309.5 iron pipe in swamp measuring Easterly on line from same section corner 0+78 descend hill, 2+00 foot of hill, 566 ft. to creek. Feb. 21, 1936.

1980 - C.F. Clark found a 2 1/2" iron pipe 2' above ground found witnessed nails in: 22" White Birch N75W 39.00 ft; 14" Jack Pine S30W 38.47 ft. (See reverse side).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 2 3/4" iron pipe 1.7 ft. above grade in small depression. Found nail in 20" Jack Pine N40E 47.00 ft. Found nail in 24" Dead White Birch N78E 39.03 ft. 27 ft. North of the centerline of East/West road at the SW corner of Section 31. Replaced 2 3/4" iron pipe with a Marquette County Survey Monument. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

6" Jack Pine N07E 44.51 ft.  
10" Maple N52W 68.19 ft. Clark NBT  
6" Maple S40W 14.54 ft.  
20" Jack Pine N40E 47.00 ft. Clark NBT  
Monument is 0.50 ft. above ground at East edge of depression.  
Bk. 5, Pg. 2



Signed by Gerald W. Carlson Date 12-28-93  
Surveyor's Michigan License No. 24589

Record No. 408

Part "A" Continued:

Referenced by nails in:

14" Jack Pine	N40°E	46.86 ft.
14" Jack Pine	S40°W	38.47 ft.
22" White Birch	N75°E	39.00 ft.

PK nail in:

8" Maple L4 R.C., Pg. 15	N50°W	68.20 ft.
-----------------------------	-------	-----------

PK nail in  
L4 R.C., Pg. 15