

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300

SHEET NO. : 1-347

For corners in

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 24W	A-2
	T 47N R 35W	M-2
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY
 RECEIVED FOR RECORD
 1993 DEC 29 AM 10:38
 REGISTER OF DEEDS
 1 PAGE 43
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2: Quarter Corner common to Section 5, T47N-R24W and Section 1, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:

- 20" Hemlock S55W, 15 1
- 6" Sugar N22E, 26 1

1953 - A tracing of the plat of the Village of Harvey and the possession of the Spear family indicates an iron pipe marker at the W 1/4 corner of Section 6. No corner accessories were given on this map.

(See reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Recent surveys of Sections 6 & 7 have indicated a found 1 1/2 inch iron pipe at the W1/4 corner of Section 6. The position corresponds to the above maps aforementioned above in Part A. The distance to the SW corner of Section 6 is 2622.61 feet. This distance checks within 0.52 feet of the 1/16 corner distance shown on the recorded plat of Scenic Hills Estates indicating that this iron pipe was used in determining that East line of that recorded plat.

No original G.L.O. evidence found.
 Replaced the found 1 1/2" pipe with a Marquette County Survey Monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 1 1/2" pipe with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 6" White Birch S43W 23.75 ft.
- 15" Spruce N40W 29.30 ft.
- 25" White Pine N10W 29.52 ft.
- 14" Triple Maple N70E 8.88 ft.

Monument is 0.4 ft. above ground. Corner falls in wooded subdivision therefore no bearing tree tags were posted.
 Bk. 4, Pg. 6

Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589



Record 347

Part "A" Continued:

An old survey map by R. Washburn, P.S. with no date on it also indicates an iron at the W 1/4 corner of Section 6.

1966 - the recorded plat of Whispering Pines Addition No. 1 indicates some sort of a marker at the W 1/4 corner of Section 6. No accessories were given.