

JOB NUMBER: 93300
SHEET NO.: 1-349
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 29 AM 10:39
REGISTER OF DEEDS
1 PAGE 51
Register of Deeds Stamp & File Number

	Located In:	Corner Code ##
1. Public Land Survey	T 47N R 24W	A-4
	T 47N R 25W	M-4
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Monday, December 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>A-4: Quarter Corner common to Section 7, T47N-R24W and Section 12, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:</p> <p>4" fir S25W, 18 1</p> <p>18" Hemlock N24E, 8 1</p>	<p>1975 - William Donnan, P.S. set a 5/8" rod and RLS cap midway and on line between SW and NW Section corner of Section 7. Referenced by:</p> <p>6" Jackpine S50W 19.44 ft.</p> <p>4" White Oak S10W 15.87 ft.</p> <p>4" Maple N70W 30.09 ft. L1 RC, Pg. 198</p> <p>Corner is also shown on the recorded plat of Shiloh No corner accessories given.</p>
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found a 5/8 inch iron RLS cap 17618 (William Donnan) that checked within 0.35 feet of being halfway and on line between the NW and SW corners of Section 7.

No original G.L.O. evidence found.

Replaced the 5/8 rod and cap with a Marquette County Survey Monument.

Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 5/8 iron with RLS cap 17618 with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify corner referenced by nails in:

4" Maple N90E 24.53 ft.

7" Oak S25W 16.30 ft. Donnan NBT

5" Maple N72W 30.34 ft. Donnan NBT

4" Maple N26E 13.36 ft.

Monument is 0.20 below grade and lands on the South side of the woods trail. The old Donnan NBT 6" Jack Pine was found dead.

Ek. 4, Pg. 10

Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589

