

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-353

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD 1993 DEC 29 AM 10:39 REGISTER OF DEEDS

Form with fields for 'Located In: MARQUETTE (County)', 'Corner Code #', and a table for survey types (Public Land Survey, Property Controlling, etc.) with grid coordinates (T47N, R24W, etc.) and corner codes (A-8, M-8).

LIBER 1 PAGE 52 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, GERALD W. CARLSON, in a field survey on Tuesday, December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (8,19) contains a black dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8: Quarter Corner common to Section 19, T47N-R24W and Section 24, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 8" Sugar S55W, 8 1; 6" Maple N72E, 37 1. 1976 - Dave Babbitt monumented a DNR 1" pipe and a 4" aluminum cap. Midway between the NW and SW corner of Section 19. Referenced by: 13" Hard Maple N80E 7.95 ft.; 11" Ironwood N55W 17.4 ft.; 13" Hard Maple S01W 17.5 ft.; L1 RC, Pg. 176

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - The distance on the DNR map indicates the distance from the West 1/4 corner of the NW 1/4 corner of 19 is 2635.20 ft. The 1993 remonumentation survey measured this 1/2 mile distances 2624.08 ft. indicating a 10.12 ft. shortage from the DNR measurement in this 1/2 mile. The intent to monument this line by Dave Babbitt was correct in the decision to proportion this line, and conclusive evidence to G.L.O. calls does not substantiate movement of his corners as monumented from the SW corner of Section 30 to the NW corner of Section 19, so accept corners as found. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found Department of Natural Resources iron pipe with aluminum cap in place referenced by nails in: 10" Ironwood N13E 18.38 ft.; 16" Maple N03E 8.47 ft. Babbitt NBT; 16" Maple S04W 17.79 ft. Babbitt NBT; 11" Maple S60W 17.14 ft. Monument is 1.0 ft. above ground stamped MCR-1993 on cap of monument (Marquette County Remonumentation). Bk. 2, Pg. 180

Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589

