

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300
SHEET NO. : 1-355
For corners in

Located In: MARQUETTE (County)

Corner Code # A-10 ✓

1. Public Land Survey	T <u>47N</u>	R <u>24W</u>	<u>A-10</u> ✓
	T <u>47N</u>	R <u>25W</u>	<u>M-10</u>
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

1993 DEC 29 AM 10:39
RECEIVED FOR RECORDING
MARQUETTE COUNTY
REGISTERED PROFESSIONAL SURVEYOR

Gerald W. Carlson
REGISTERED PROFESSIONAL SURVEYOR

LIBER 1 PAGE 48
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Wednesday, December 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-10: Quarter Corner common to Section 30, T47N-R24W and Section 25, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:

- 24" Hemlock S52W, 27 1
- 14" Sugar N14E, 10 1

1976 - David Babbitt set a 1' pipe & 4" aluminum DNR cap midway between the NW and SW corner of Section 30, Referenced by:

- 8" Sugar Maple N70E 11.00 ft.
- 10" Sugar Maple S20E 27.15 ft.
- 12" Sugar Maple N76W 10.60 ft.

(See reverse side)
L1 RC, Pg. 172

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - The distance on the DNR map indicates the distance from the West 1/4 corner of the NW 1/4 corner of 19 is 2635.20 ft. The 1993 remonumentation survey measured this 1/2 mile distances 2624.08 ft. indicating a 10.12 ft. shortage from the DNR measurement in this 1/2 mile. The intent to monument this line by Dave Babbit was correct in the decision to proportion this line, and conclusive evidence to G.L.O. calls does not substantiate movement of his corners as monumented from the SW corner of Section 30 to the NW corner of Section 19, so accept corners as found. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found Department of Natural Resources iron pipe and aluminum cap referenced by nails in:

- 16" Maple N68W 10.50 ft. Babbitt NBT
- 10" Maple N75E 11.43 ft. Babbitt NBT
- 20" Maple S25E 19.87 ft.
- 17" Maple S31W 39.54 ft.

Monument 1.0 ft. above ground.
All distances above were measured to nails in trees with CoVN washers. Stamped MCR-1993 on cap of monument (Marquette County Remonumentation).
Bk. 3, Pg. 154

Signed by Gerald W. Carlson Date 12-23-93
Surveyor's Michigan License No. 24589



Record No. 355

Part "A" Continued:

1988 - Glenn Van Neste found a DNR monument referenced by:

13" Maple	Az.	288°	10.50 ft.
10" Maple	Az.	72°	11.44 ft.
18" Maple	Az.	153°	19.94 ft.
15" Maple	Az	211°	39.57 ft.

*AK 300
900
A.*