

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-356

For corners in

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 24W	A-11 ✓
	T 47N R 25W	M-11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
 MARQUETTE COUNTY
 MICHIGAN
 1993 DEC 29 AM 10:39
 REGISTER OF DEEDS

LIBER 1 PAGE 53
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11: Section Corner common to Sections 30 and 31, T47N-R24W 1976 - David Babbitt found a 1 1/4" pipe not on record and Sections 25 and 36, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
 14" Y. Birch S12E, 14 l
 14" Sugar N14W, 26 l

1976 - David Babbitt found a 1 1/4" pipe not on record - fits G. L. O. discription of being "in valley" and fits other corner locations in the area well - replaced pipe with D. N. R. monument.
 Referenced by:
 4" Sugar Maple S10W 24.8 ft.
 13" Sugar Maple S72E 29.0 ft.
 6" Red Maple S60E 16.85 ft.
 4" Sugar Maple N41W 17.75 ft. L1 RC, Pg. 167

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - remonumentation survey recovered a DNR 1" pipe with 4" aluminum cap. The distance corresponds to corners North and South. Left DNR 1" pipe and 4" aluminum cap as found.
 Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found Department of Natural Resources iron pipe with aluminum cap in place referenced by nails in:
 10" Maple N65E 16.95 ft.
 14" Maple S77E 29.42 ft. Babbitt NBT
 6" Maple S13W 24.76 ft. Babbitt NBT
 9" Maple S77W 12.42 ft.
 Monument is 1.0 ft. above ground stamped MCR-1993 on cap of monument (Marquette County Remonumentation).
 Bk. 2, Pg. 146

Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589

