COMMISSION

	93300				
SHEET NO. : 1-3	58				

LAND CORNER RECORDATION CERTIFICATE

	Corners in	Filing Require	ment of Act 74, Mich.	P.A. 1970	1					
	MARQUETTE (County)	Located In:	Corner Code ##			が 記 記	3 6		HARO	
1.	Public Land Survey	T47N R 24W T47N R 25W T46N R 24W T46N R 25W	M-13 A-1 M-1	į į		E TO MISSER.	67	ner so	MICHIGAL MICHIGAL	
	Property Controlling in Section Miscellaneous Property in Sec.	S T R S T R S T R S T R		LIBER	1 Position of D	ACE & C	55 contractions of the second	ວ ີ [Numbe	er
		Recorded Plat			- АВ	c o	E F (зн	IJК	LM
do l in li cur Mar abo Cou exp	nereby certify that under re ines 1 and 2 above were rent manual of survey inst nagement or by a decree o ive were in conformance w urt of Law; established, ressed below:	in a field survey on Thursday. equirements of P.A. 74, Michigan P.A. of in conformance with regulations and ructions of the United States Departs fa Court of Law and/or that the corner with the rules of the Michigan Board of re-established, monumented, re-macorners, all in the same town and a corners, all in the same town and a corners, all in the same town and a corners.	of 1970, the corner points mer drules therefore as required ment of the Interior, Bureau of points mentioned in lines 3, i Land Surveyors or by a Dec- tonumented, recovered, for	ntioned d in the of Land 4 and 5 ree of a und as	3 4 7 7 5 6 18 7 8 19 9 10 30 11 12 31	20-29			-11	12
Δ		•	/or subsequent restoration	on.	13	32	33	34	35	36
A. Description of original monument and accessories and/or subsequent restoration: A-13: Section Corner common to Section 31, T47N-R24W; Section 6, T46N-R24W; Section 1, T46N-R25W; and Section 36 T47N-R25W. 1844: William A. Burt's original survey notes at the correct bearing and distar describe the corner monument as a wood post referenced by: 16" Hemlock S85W, 22 1 26" Hemlock N18E, 54 1 26" Hemlock N18E, 54 1 12" Maple, S16W, 23.82 ft. 8" Maple, S80E, 18.44 ft. 4" Tw. Maple, N45E, 22.03 ft. 8" Tw. Maple, N71W, 37.06 ft. 11							od post from th the	remain		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found G. Carlson concrete monument as set in 1980. Replaced with a Marquette County Survey Monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced concrete monument with 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

S16W 23.78 ft, Carlson NBT 14" Maple 8" Maple \$80E 18.48 ft. Carlson NBT

N45E 22.03 ft. Carlson NBT 4" Maple

10" Twin Maple N71W 37.00 ft. Carlson NBT

Monument is 0.8 ft. above ground.

Bk. 3, Pg. 156

Gerald W Carl 24589 Surveyor's Michigan License No. _

GERALD W. CARLSON SURVEYOR No. 24585

VISED MAY 14, 1975 REVISED JAN., 1983