

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300  
SHEET NO. : 1-359  
For corners in

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 24W	B-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1993 DEC 29 AM 10:39

REGISTER OF DEEDS

1 PAGE 56

Register of Deeds Stamp & File Number

LIBER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Saturday, December 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<p>B-13: South Quarter Corner Section 31, T47N-R24W</p> <p>1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:</p> <p>7" Fir N24E, 25 l</p> <p>8" Sugar N53W, 31 l</p>	<p>1980 - G. Carlson set a 5/8 x 18" iron with RLS cap proportionately on line between the SW corner of Section 31, and the South 1/4 corner of Section 33 on East edge of N-S dirt road. Referenced by:</p> <p>12" Maple North, 36.00 ft.</p> <p>6" White Birch N78E 12.25 ft.</p> <p>7" White Pine S48E 37.70 ft.</p> <p>5" Maple N89W 24.14 ft. L4 RC, Pg. 24</p> <p>15.51' East of North 1/4 corner Sec. 6, T46N-R24W</p>
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron G. Carlson cap on the East side of the North/South dirt road. Distances to the West 0.22 from the 1980 survey and the distance East is within 0.28 ft. from the 1980 survey.

Replaced 5/8" iron with GWC cap with Marquette County Survey Monument. Peer group ratification 12-5-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 5/8" iron with RLS cap 24589 with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Maquette County Survey Monument stamped to identify the corner referenced by nails in:

11" Maple North 36.05 ft. Carlson NBT

7" Birch N80E 12.50 ft. Carlson NBT

12" Maple S52W 31.03 ft.

13" Maple N77W 20.99 ft.

Monument is 0.55 ft. below ground just East of the East edge of the woods road just North of a fork in the road.

Signed by Gerald W. Carlson Date 12-23-93

Surveyor's Michigan License No. 24589

