

JOB NUMBER: 93300

SHEET NO. : 1-360

For corners in

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>24W</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 57  
 Register of Deeds Stamp & File Number  
 RECEIVED FOR RECORD  
 1983 DEC 29 AM 10:39  
 REGISTER OF DEEDS  
 MARQUETTE COUNTY MICHIGAN

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Saturday, December 11, 1983, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-13: Section Corner common to Sections 31 and 32, T47N-R24W. 1980 - G. Carlson set a 5/8 by 18 iron RLS cap proportionately on line between the SW corner of Section 31 and the South quarter corner of Section 33, at the toe of an East facing slope referenced by:

- 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
  - 10" Hemlock N38E, 37 l
  - 10" Y. Birch N54W, 51 l
- 5" Maple N33E 21.45 ft.
- 5" Maple S87E 3.75 ft.
- 6" Maple S16E 24.96 ft.
- 14" Oak N81W 13.04 ft.
- 31.02 ft. East of the NW corner of Sec. 5, T46N-R24W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found a 5/8" iron with unreadable cap. Distance 1/2 mile West checked within 0.28 ft. Distance 1 mile East checked within the 0.14 ft. Replaced 5/8 iron and RLS cap with Marquette County survey monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 5/8" iron with RLS cap 24589 with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 6" Maple N37E 21.68 ft. Carlson NBT
- 6" Maple S88E 3.76 ft. Carlson NBT
- 8" Maple S15E 25.07 ft. Carlson NBT
- 5" Maple S32W 37.46 ft.

Monument is flush with ground at toe of slope.  
 Bk. 2, Pg. 118

Signed by Gerald W. Carlson  
 Surveyor's Michigan License No. 24589

Date 12-23-93

