

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-361

For corners in

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

_____ MARQUETTE _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>24W</u>	D-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 58
Register of Deeds Stamp & File Number

1993 DEC 29 AM 10:39
RECEIVED FOR RECORD
MARQUETTE COUNTY
MICHIGAN
REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Saturday, December 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13: South Quarter Corner Section 32, T47N-R24W	1980 - G. Carlson set a 5/8 x 18 iron with RLS cap
1844: William A. Burt's original survey notes	proportionately on line between the SW cor. Sec. 31
describe the corner monument as a wood post	and the South 1/4 cor. Sec. 33, 35 ft. South of an
referenced by:	old East/West fence line. No original G.L.O. evidence
10" Cedar N52E, 26 1	found. Referenced by:
14" Y.Birch N58W, 18 1	8" Balsam S11W 9.92 ft. 6" Cedar N73W 5.04 ft.
	11" Cedar N11E 5.45 ft. 4" Cedar S82E 11.16 ft.
	26.40' East of the N 1/4 cor. Sec. 5, T46N-R24W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Searched area previously monumented in 1980 with the 5/8" iron with RLS cap found no evidence of corner. Apparently the corner has been pulled out. Set a Marquette County Survey Monument equidistant and on line between the SW and SE corners of Section 32. The proportioned G.L.O. distance to the river, East of this corner checks within 16 ft. The river in this area is changing directions at a bend and is difficult to determine the actual position that the original surveyors crossed. The distances East and West from the 1/4 corner are 2609.23' compared to 2609.76' in the 1980 survey. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

Power Pole N15E 33.08 ft.
12" Maple N86E 49.19 ft.
12" Maple S41E 66.77 ft.
8" Cedar N29W 17.18 ft.
Bk. 2, Pg. 122

Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589

